

SEISMIC HAZARD EVALUATION OF THE SUNLAND 7.5-MINUTE QUADRANGLE, LOS ANGELES COUNTY, CALIFORNIA

1998



DEPARTMENT OF CONSERVATION
Division of Mines and Geology

THE RESOURCES AGENCY
MARY D. NICHOLS
SECRETARY FOR RESOURCES

STATE OF CALIFORNIA
GRAY DAVIS
GOVERNOR

DEPARTMENT OF CONSERVATION
DARRYL YOUNG
DIRECTOR



DIVISION OF MINES AND GEOLOGY
JAMES F. DAVIS, *STATE GEOLOGIST*

Copyright © 2000 by the California Department of Conservation. All rights reserved. No part of this publication may be reproduced without written consent of the Department of Conservation.

"The Department of Conservation makes no warranties as to the suitability of this product for any particular purpose."

**SEISMIC HAZARD EVALUATION OF THE
SUNLAND 7.5-MINUTE QUADRANGLE,
LOS ANGELES COUNTY, CALIFORNIA**

DIVISION OF MINES AND GEOLOGY'S PUBLICATION SALES OFFICES:

Southern California Regional Office
655 S. Hope Street, Suite 700
Los Angeles, CA 90017
(213) 239-0878

Publications and Information Office
801 K Street, MS 14-31
Sacramento, CA 95814-3531
(916) 445-5716

Bay Area Regional Office
185 Berry Street, Suite 210
San Francisco, CA 94107-1728
(415) 904-7707

CONTENTS

PREFACE	vii
INTRODUCTION	1
SECTION 1. LIQUEFACTION EVALUATION REPORT: Liquefaction Zones in the Sunland 7.5-Minute Quadrangle, Los Angeles County, California	3
PURPOSE	3
Background.....	4
Scope and Limitations	4
PART I	5
STUDY AREA LOCATION AND PHYSIOGRAPHY	5
GEOLOGIC CONDITIONS	5
GROUND-WATER CONDITIONS.....	9
PART II.....	10
EVALUATING LIQUEFACTION POTENTIAL	10
LIQUEFACTION OPPORTUNITY.....	11
LIQUEFACTION SUSCEPTIBILITY	11
LIQUEFACTION ZONES	13
ACKNOWLEDGMENTS	14
REFERENCES	14
SECTION 2. EARTHQUAKE-INDUCED LANDSLIDE EVALUATION REPORT: Earthquake-Induced Landslide Zones in the Sunland 7.5-Minute Quadrangle, Los Angeles County, California	17
PURPOSE	17

Background	18
Scope and Limitations	18
PART I	19
STUDY AREA LOCATION AND PHYSIOGRAPHY	19
GEOLOGIC CONDITIONS	19
PART II	26
EARTHQUAKE-INDUCED LANDSLIDE GROUND SHAKING OPPORTUNITY	26
EARTHQUAKE-INDUCED LANDSLIDE HAZARD POTENTIAL	27
EARTHQUAKE-INDUCED LANDSLIDE ZONE	29
ACKNOWLEDGMENTS	31
REFERENCES	31
AIR PHOTOS	33
APPENDIX A Sources of Rock Strength Data	34
SECTION 3	GROUND SHAKING EVALUATION REPORT: Potential Ground Shaking in the Sunland 7.5-Minute Quadrangle, Los Angeles County, California
	35
PURPOSE	35
EARTHQUAKE HAZARD MODEL	36
APPLICATIONS FOR LIQUEFACTION AND LANDSLIDE HAZARD ASSESSMENTS	40
USE AND LIMITATIONS	40
REFERENCES	42

ILLUSTRATIONS

Table 1.1. Units of the Southern California Areal Mapping Project (SCAMP) nomenclature used in the San Fernando Valley.....	6
Table 1.2. General geotechnical characteristics and liquefaction susceptibility of younger Quaternary units.	8
Table 2.1. Summary of the shear strength statistics for the Sunland Quadrangle.....	25
Table 2.2. Summary of the shear strength groups for the Sunland Quadrangle.....	25
Table 2.3. Hazard potential matrix for earthquake-induced landslides in the Sunland Quadrangle.....	29
Figure 2.1. Yield Acceleration vs. Newmark Displacement for the Pacoima-Kagel Canyon Strong- Motion Record From the 17 January 1994 Northridge, California Earthquake. Record from California Strong Motion Instrumentation Program (CSMIP) Station 24088.....	28
Figure 3.1. Sunland 7.5-Minute Quadrangle and portions of adjacent quadrangles, 10% exceedance in 50 years peak ground acceleration (g)—Firm rock conditions.....	37
Figure 3.2. Sunland 7.5-Minute Quadrangle and portions of adjacent quadrangles, 10% exceedance in 50 years peak ground acceleration (g)—Soft rock conditions.	38
Figure 3.3. Sunland 7.5-Minute Quadrangle and portions of adjacent quadrangles, 10% exceedance in 50 years peak ground acceleration (g)—Alluvium conditions.....	39
Figure 3.4. Sunland 7.5-Minute Quadrangle and portions of adjacent quadrangles, 10% exceedance in 50 years peak ground acceleration—Predominant earthquake.....	41
Plate 1.1. Quaternary geologic map of the Sunland Quadrangle.	
Plate 1.2. Historically highest ground-water contours and borehole log data locations, Sunland Quadrangle.	
Plate 2.1: Landslide inventory, shear test sample location, and areas of significant grading, Sunland Quadrangle	

PREFACE

With the increasing public concern about the potential for destructive earthquakes in northern and southern California, the State Legislature passed the Seismic Hazards Mapping Act in 1990. The purpose of the Act is to protect the public from the effects of strong ground shaking, liquefaction, landslides or other ground failure, and other hazards caused by earthquakes. The program and actions mandated by the Seismic Hazards Mapping Act closely resemble those of the Alquist-Priolo Earthquake Fault Zoning Act (which addresses only surface fault-rupture hazards) and are outlined below:

1. **The State Geologist** is required to delineate the various "seismic hazard zones."
2. **Cities and Counties**, or other local permitting authorities, must regulate certain development "projects" within the zones. They must withhold the development permits for a site within a zone until the geologic and soil conditions of the project site are investigated and appropriate mitigation measures, if any, are incorporated into development plans.
3. **The State Mining and Geology Board (SMGB)** provides additional regulations, policies, and criteria to guide cities and counties in their implementation of the law. The SMGB also provides criteria for preparation of the Seismic Hazard Zone Maps (Web site <http://www.consrv.ca.gov/dmg/shezp/zoneguid/>) and for evaluating and mitigating seismic hazards.
4. **Sellers (and their agents)** of real property within a mapped hazard zone must disclose at the time of sale that the property lies within such a zone.

As stated above, the Act directs the State Geologist, through the Division of Mines and Geology (DMG) to delineate seismic hazard zones. Delineation of seismic hazard zones is conducted under criteria established by the Seismic Hazards Mapping Act Advisory Committee and its Working Groups and adopted by the California SMGB.

The Official Seismic Hazard Zone Maps, released by DMG, which depict zones of required investigation for liquefaction and/or earthquake-induced landslides, are available from:

BPS Reprographic Services
149 Second Street
San Francisco, California 94105
(415) 512-6550

Seismic Hazard Evaluation Reports, released as Open-File Reports (OFR), summarize the development of the hazard zone map for each area and contain background documentation for use

by site investigators and local government reviewers. These Open-File Reports are available for reference at DMG offices in Sacramento, San Francisco, and Los Angeles. Copies of the reports may be purchased at the Sacramento, Los Angeles, and San Francisco offices. In addition, the Sacramento office offers prepaid mail order sales for all DMG OFRs. **NOTE: The Open-File Reports are not available through BPS Reprographic Services.**

DIVISION OF MINES AND GEOLOGY OFFICES

Geologic Information and Publications Office
801 K Street, MS 14-33
Sacramento, CA 95814-3532
(916) 445-5716

Bay Area Regional Office
185 Berry Street, Suite 210
San Francisco, CA 94107-1728
(415) 904-7707

Southern California Regional Office
655 S. Hope Street, Suite 700
Los Angeles, CA 90017
(213) 239-0878

WORLD WIDE WEB ADDRESS

Seismic Hazard Evaluation Reports and additional information on seismic hazard zone mapping in California are available on the Division of Mines and Geology's Internet homepage:
<http://www.consrv.ca.gov/dmg/shezp/>

INTRODUCTION

The Seismic Hazards Mapping Act (the Act) of 1990 (Public Resources Code, Chapter 7.8, Division 2) directs the California Department of Conservation, Division of Mines and Geology (DMG) to delineate seismic hazard zones. The purpose of the Act is to reduce the threat to public health and safety and to minimize the loss of life and property by identifying and mitigating seismic hazards. Cities, counties, and state agencies are directed to use the seismic hazard zone maps in their land-use planning and permitting processes. The Act requires that site-specific geotechnical investigations be performed prior to permitting most urban development projects within the hazard zones. Evaluation and mitigation of seismic hazards are to be conducted under guidelines established by the California State Mining and Geology Board (1997; also available on the Internet at <http://www.consrv.ca.gov/dmg/pubs/sp/117/>).

The Act also directs SMGB to appoint and consult with the Seismic Hazards Mapping Act Advisory Committee (SHMAAC) in developing criteria for the preparation of the seismic hazard zone maps. SHMAAC consists of geologists, seismologists, civil and structural engineers, representatives of city and county governments, the state insurance commissioner and the insurance industry. In 1991 SMGB adopted initial criteria for delineating seismic hazard zones to promote uniform and effective statewide implementation of the Act. These initial criteria provide detailed standards for mapping regional liquefaction hazards. They also directed DMG to develop a set of probabilistic seismic maps for California and to research methods that might be appropriate for mapping earthquake-induced landslide hazards.

In 1996, working groups established by SHMAAC reviewed the prototype maps and the techniques used to create them. The reviews resulted in recommendations that the 1) process for zoning liquefaction hazards remain unchanged and that 2) earthquake-induced landslide zones be delineated using a modified Newmark analysis.

This Seismic Hazard Evaluation Report summarizes the development of the hazard zone map for each area. The process of zoning for liquefaction uses a combination of Quaternary geologic mapping, historic high-water-table information, and subsurface geotechnical data. The process for zoning earthquake-induced landslides incorporates earthquake loading, existing landslide features, slope gradient, rock strength, and geologic structure. Probabilistic seismic hazard maps, which are the underpinning for delineating seismic hazard zones, have been prepared for peak ground acceleration, mode magnitude, and mode distance with a 10% probability of exceedance in 50 years (Petersen and others, 1996) in accordance with the mapping criteria.

This evaluation report summarizes seismic hazard zone mapping for potentially liquefiable soils and earthquake-induced landslides in the Sunland 7.5-Minute Quadrangle (scale 1:24,000).

SECTION 1

LIQUEFACTION EVALUATION REPORT

Liquefaction Zones in the Sunland 7.5-Minute Quadrangle, Los Angeles County, California

**By
Christopher J. Wills**

**California Department of Conservation
Division of Mines and Geology**

PURPOSE

The Seismic Hazards Mapping Act (the Act) of 1990 (Public Resources Code, Chapter 7.8, Division 2) directs the California Department of Conservation, Division of Mines and Geology (DMG) to delineate Seismic Hazard Zones. The purpose of the Act is to reduce the threat to public health and safety and to minimize the loss of life and property by identifying and mitigating seismic hazards. Cities, counties, and state agencies are directed to use the seismic zone maps in their land-use planning and permitting processes. The Act requires that site-specific geotechnical investigations be performed prior to permitting most urban development projects within the hazard zones. Evaluation and mitigation of seismic hazards are to be conducted under guidelines established by the California State Mining and Geology Board (1997; also available on the Internet at <http://www.consrv.ca.gov/pubs/sp/117/>).

This evaluation report summarizes seismic hazard zone mapping for potentially liquefiable soils in the Sunland 7.5-minute Quadrangle (scale 1:24,000). This section and Section 2 addressing earthquake-induced landslides, are part of a series that will summarize development of similar hazard zone maps in the state (Smith, 1996). Additional information on seismic hazards zone mapping in California can be accessed on DMG's Internet homepage: <http://www.consrv.ca.gov/dmg/shezp/>

BACKGROUND

Liquefaction-induced ground failure has historically been a major cause of earthquake damage in southern California. During the 1971 San Fernando and 1994 Northridge earthquakes, significant damage to roads, utility pipelines, buildings, and other structures in the Los Angeles area was caused by liquefaction-induced ground displacement.

Localities most susceptible to liquefaction-induced damage are underlain by loose, water-saturated granular sediments within 40 feet of the ground surface. These geological and ground-water conditions exist in parts of southern California, most notably in some densely populated valley regions and alluviated floodplains. In addition, the opportunity for strong earthquake ground shaking is high because of the many nearby active faults. The combination of these factors constitutes a significant seismic hazard in the southern California region in general, as well as in the Sunland Quadrangle.

SCOPE AND LIMITATIONS

Evaluation for potentially liquefiable soils is generally confined to areas covered by Quaternary sedimentary deposits. Such areas consist mainly of alluviated valleys, floodplains, and canyon regions. The evaluation is based on earthquake ground shaking, surface and subsurface lithology, geotechnical soil properties, and ground-water depth data, most of which are gathered from a variety of sources. The quality of the data used varies. Although selection of data used in this evaluation was rigorous, the state of California and the Department of Conservation make no representations or warranties regarding the accuracy of the data obtained from outside sources.

Liquefaction zone maps are intended to prompt more detailed, site-specific geotechnical investigations as required by the Act. As such, liquefaction zone maps identify areas where the potential for liquefaction is relatively high. They do not predict the amount or direction of liquefaction-related ground displacements, or the amount of damage to facilities that may result from liquefaction. Factors that control liquefaction-induced ground failure are the extent, depth and thickness of liquefiable sediments, depth to ground water, rate of drainage, slope gradient, proximity to free-face conditions, and intensity and duration of ground shaking. These factors must be evaluated on a site-specific basis to determine the potential for ground failure at any given project site.

Information developed in the study is presented in two parts: physiographic, geologic, and hydrologic conditions in PART I, and liquefaction potential, opportunity, susceptibility, and zoning evaluations in PART II.

PART I

STUDY AREA LOCATION AND PHYSIOGRAPHY

The Sunland Quadrangle covers an area of about 62 square miles in western Los Angeles County. The community of Sunland, which is about 14 miles north-northwest of the Los Angeles Civic Center, and the adjacent community of Tujunga, both parts of the City of Los Angeles, are scattered across the northern San Fernando Valley floor in the southern part of the quadrangle. North of the San Fernando Valley, the San Gabriel Mountains cover about four-fifths of the Sunland Quadrangle. Except for a small fringe of unincorporated Los Angeles County land along the mountain front most of the land in the mountains lies within the Angeles National Forest. South of Tujunga Valley, the northwestern end of the Verdugo Mountains extends into the southern edge of the quadrangle. Canyons within the mountains extend south to the San Fernando Valley.

The San Fernando Valley is an east-trending structural trough within the Transverse Ranges of southern California. The San Gabriel Mountains that bound it to the northeast are composed of plutonic and metamorphic rocks that are being thrust over the valley from the north. As the range has been elevated and deformed, the San Fernando Valley has subsided and filled with sediment.

The northern portion of the San Fernando Valley in the Sunland Quadrangle has received sediment from drainage systems originating in the San Gabriel Mountains. The larger systems, Little Tujunga and Big Tujunga washes, are large river systems that have their sources in the steep, rugged San Gabriel Mountains. Each of these drainage systems has a drainage basin of tens of square miles within the mountains and can carry a large volume of sediment. The alluvial fans deposited by these drainage systems have their apexes outside of the Sunland Quadrangle in the southern San Fernando Quadrangle and cover most of the Van Nuys and Burbank quadrangles to the south. Composition of these deposits is dependent on the source areas of the drainages. Drainages with source areas in the San Gabriel Mountains primarily have granitic or other plutonic rocks in their drainage basins. The deposits of these streams, consequently are composed of sandy alluvium.

GEOLOGIC CONDITIONS

Surface Geology

Late Quaternary geologic units in the San Fernando Valley area were completely re-mapped for this study and a concurrent study by engineering geologist Chris Hitchcock of William Lettis and Associates. Lettis and Associates received a grant from the National Science Foundation (NSF) to study the activity of the Northridge Hills uplift. As part of the research for this study, Hitchcock mapped Quaternary surficial units by interpreting their geomorphic expression on aerial photographs and topographic maps. The primary source for this work was 1938 aerial photographs taken by the U.S. Department of Agriculture (USDA). His interpretations were checked and extended for this study using 1952 U.S.D.A. aerial photos, 1920's topographic maps

and subsurface data. The resulting map (Hitchcock and Wills, 1998) represents a cooperative effort to depict the Quaternary geology of the San Fernando Valley combining surficial geomorphic mapping and information about subsurface soils engineering properties. The portions of this map that cover the Sunland Quadrangle are reproduced as Plate 1.1.

In preparing the Quaternary geologic map for the Sunland Quadrangle, geologic maps prepared by Barrows and others, (1975), Crook and others (1987), Oakeshott (1958), Tinsley and others (1985), Dibblee (1991) and Yerkes (1996) were referred to. We began with the map of Yerkes (1996) as a digital files in the DMG Geographic Information System (GIS). The Quaternary geology shown on the map of Yerkes (1996) was compiled from Tinsley and others (1985) and Oakeshott (1958). For the liquefaction portion of this study, we did not review or revise the mapping of bedrock units by Yerkes (1996), except for the contacts between bedrock and Quaternary units. However, changes to the bedrock geology were made for the landslide portion of this study, and the changes are described in the landslide portion (Section 2) of this evaluation report. Within the San Fernando Valley mapping of Quaternary units by Hitchcock (and for this study) was used to refine and substantially revise this mapping. For this map (Plate 1.1), geologic units were defined based on geomorphic expression of Quaternary units (interpreted from aerial photographs and historic topographic maps) and subsurface characteristics of those units (based on borehole data). In the Tujunga Valley portion of the Sunland Quadrangle, Quaternary mapping by Crook and others (1987) was compiled for this map. The nomenclature of the Southern California Areal Mapping Project (SCAMP) (Morton and Kennedy, 1989) was applied to all Quaternary units (Table 1.1).

	Alluvial Fan Deposits	Alluvial Valley Deposits	Age
Active	Qf- active fan ????? Qw- active wash		Holocene?
Young	Qyf2 Qyf1	Qyt	
Old	Qof1		Pleistocene?
Very old	Qvof1	Qvoa*	Pleistocene

*May have been alluvial fan, depositional form not preserved

Table 1.1. Units of the Southern California Areal Mapping Project (SCAMP) nomenclature used in the San Fernando Valley.

The Quaternary geologic map (Plates 1.1 and 1.2) shows that the oldest alluvial units in the Sunland Quadrangle are found on the south flank of the San Gabriel Mountains. The Saugus Formation, a Pleistocene alluvial unit, is exposed in the core of a syncline north of the Sierra Madre Fault and south of a series of thrust faults that place crystalline basement rocks over Tertiary sedimentary rock.

Overlying Saugus Formation along the front of the San Gabriel Mountains are very old alluvial deposits (Qvoa, Qvofl, and Qab). These deposits are uplifted, deformed, commonly have red (mature) soils and are typically dense to very dense. Qvoa consists of intensely deformed older alluvium along the San Fernando segment of the Sierra Madre fault zone. Its age in relation to the other units is not known. Qvofl exists as remnants of alluvial surfaces on tops of ridges between Pacoima Wash and Big Tujunga Canyon. Qab is mixed alluvial and colluvial material deformed along the Sierra Madre Fault Zone.

Older alluvium (Qofl) consists of remnants of alluvial fans now uplifted as terraces along the edge of Tujunga Wash. Older alluvial fans are also found in the uplifted area between Pacoima and Big Tujunga Canyons. These deposits are composed of sand, silt, and gravel and commonly form recognizable alluvial fans. The fan surfaces are no longer active because continuing deformation has either lifted them out of the area of deposition or because they have been buried by later alluvium. The younger alluvial fans can be subdivided into young (Qyf1 and Qyf2) and active (Qf, Qw) fan deposits on the basis of geomorphology. Young alluvial fans are described below.

Younger alluvial fans of Big Tujunga and Little Tujunga Canyons

Tujunga Wash has a drainage basin of about 90 square miles in rugged mountainous terrain that includes peaks up to 5000 feet in altitude. It is divided into two main branches, Little Tujunga Canyon to the west and Big Tujunga Canyon to the east. These two streams merge in the Tujunga Valley, where they form a broad wash. Deposits in the wash are composed of sandy gravel with boulders. The Tujunga Wash ends at Hansen Dam Flood Control Basin, built where the wash had cut through the northwestern end of the Verdugo Mountains. Hansen Dam marks the apex of the main Tujunga Wash portion of the Pacoima-Tujunga fan, which spreads south from the Sunland Quadrangle.

Subsurface Geology and Geotechnical Characteristics

The geologic units described above and listed in Table 1.2 were primarily mapped from their surface expression, especially geomorphology, as displayed on aerial photos and old topographic maps. The geomorphic mapping was compared with the subsurface properties described in about 50 borehole logs in the study area. Subsurface data used for this study include the database compiled by John Tinsley for previous studies (Tinsley and Fumal, 1985; Tinsley and others, 1985), a database of shear wave velocity measurements originally compiled by Walter Silva (Wills and Silva, 1998), and additional data collected for this study. Subsurface data were collected for this study at Caltrans, the California Department of Water Resources, the Regional Water Quality Control Board. In general, the data gathered for geotechnical studies appear to be complete and consistent. Data from environmental geology reports filed with the Water Quality Control Board are well distributed areally and provide reliable information on water levels. Geotechnical data, particularly SPT blow counts, from environmental studies are sometimes less reliable however, due to non-standard equipment and incomplete reporting of procedures.

Geologic Map Unit	Material Type	Consistency	Liquefaction Susceptibility
Qw, stream channels	sand, gravelly sand	loose-moderately dense	high
Qf, active alluvial fans	silty sand, sand	loose-moderately dense	high
Qyf2, younger alluvial fans	silty sand, sand, minor clay	loose-moderately dense	high
Qyf1, young alluvial fan	silty sand, sand, minor clay	loose-moderately dense	high
Qof1, older alluvial fan	sand & gravel	Moderately dense	low
Qvoa, Qvof1, very old alluvium	clay-silty sand	dense-very dense	low

Table 1.2. General geotechnical characteristics and liquefaction susceptibility of younger Quaternary units.

Data from previous databases and additional borehole logs were entered into the DMG GIS database. Locations of all exploratory boreholes considered in this investigation are shown on Plate 1.2. Construction of cross sections from the borehole logs, using the GIS, enabled the correlation of soil types from one borehole to another and outlining of areas of similar soils.

Descriptions of characteristics of geologic units recorded on the borehole logs are given below. These descriptions are generalized but give the most commonly encountered characteristics of the unit (see Table 1.2).

Saugus Formation: Qs, Qsu

The Pleistocene Saugus Formation is an alluvial unit that may not always be distinguished from younger overlying alluvium in borehole logs. We were not able to find logs of boreholes on the Sunland Quadrangle where Saugus Formation was encountered. On other quadrangles, it is described as "sandstone." In some locations, dense or very dense sand may be Saugus Formation but also could be old or very old alluvium.

Very old alluvium: Qvoa, Qvof1

Very old alluvium, mapped along the Sierra Madre Fault, is also not represented in our subsurface data for the Sunland Quadrangle. At the surface this material is sand and gravelly sand.

Older alluvium: Qof1

Older alluvium is distinguished from younger alluvium by being uplifted and usually incised by younger drainages and by having relatively even tonal patterns on pre-development aerial photographs. In contrast, younger alluvium typically has a braided stream tonal pattern even where those stream channels have no geomorphic expression. Qof1 consists of remnants of small alluvial fans in the Tujunga Valley and uplifted surfaces in the upper Little Tujunga Canyon and adjacent areas. Older alluvium usually occupies uplifted areas at the mountain front, because relatively little large-scale development has occurred here, this material is also not represented in our subsurface data for the Sunland Quadrangle.

Younger alluvium Qyf1, Qyf2, Qw

Within an alluvial fan, the different generations of younger alluvium can be distinguished by their geomorphic relationships. In the subsurface, it is not possible to distinguish among the generations on an alluvial fan. There may simply be too little difference in age among these units, which probably range from mid-Holocene to historic, for any differences in density or cementation to have formed.

Big Tujunga and Little Tujunga Canyons

The alluvium of Big Tujunga and Little Tujunga canyons is found mainly in channel deposits in the mountains and in the Tujunga Wash. The wash deposits are composed of sand, gravelly sand and silty sand, with some layers of gravel. SPT blow counts show that this material is loose to very dense, although some of the higher blow counts may be due to impact on large clasts in gravelly layers.

Artificial fill (af)

In the Sunland Quadrangle artificial fills large enough to show at the scale of mapping include the Hansen Dam, and engineered fill for freeways. These units were compiled from the digital map of Yerkes (1996).

GROUND-WATER CONDITIONS

The San Fernando Valley ground-water basin is a major source of domestic water for the City of Los Angeles and, as a result, has been extensively studied. The legal rights to water in the ground within the San Fernando Valley were the subject of a lawsuit by the City of Los Angeles against the City of San Fernando and other operators of water wells in the basin. The "Report of

Referee" (California State Water Rights Board, 1962) contains information on the geology, soils and ground-water levels of the San Fernando Valley.

The Report of Referee shows that ground water reached its highest levels in 1944, before excessive pumping caused drawdowns throughout the basin. Management of the ground-water resources led to stabilizing of ground-water elevations in the 1960's and, in some cases, rise of ground-water elevations in the 1970's and 1980's to levels approaching those of 1944 (Blevins, 1995).

In order to consider the historically highest ground-water level in liquefaction analysis, the 1944 ground-water elevation contours (California State Water Rights Board 1962, Plate 29) were digitized. A three-dimensional model was created from the digitized contours giving a ground-water elevation at any point on a grid. The ground-water elevation values in this grid were then subtracted from the surface elevation values from the USGS Digital Elevation Model (DEM) for the Sunland Quadrangle. The difference between the surface elevation and the ground-water elevation is the ground-water depth. Subtracting the ground-water depth grid from the DEM results in a grid of ground-water depth values at any point where the grids overlapped.

The resulting grid of ground-water depth values showed several artifacts of the differences between the sources of ground-water elevation data and surface elevation data. The ground-water elevations were interpreted from relatively few measurements in water wells. The USGS DEM is a much more detailed depiction of surface elevation, it also shows man made features such as excavations or fills that have changed the surface elevations. Most of these surface changes occurred after the ground-water levels were measured in 1944. The ground-water depth contours were smoothed and obvious artifacts removed to create a ground-water depth map. Ground-water levels from borehole data collected for this study were compared with the depths on the combined map. Borehole data led to some refinements of the final ground-water depth contours (Plate 1.2).

The ground-water depth map shows areas of shallow ground water north Hansen Dam and in the western Tujunga. Ground water is also relatively shallow in all canyons in the San Gabriel Mountains according to records that we have obtained. In general, it appears that relatively shallow and impermeable bedrock underlying the canyon alluvium helps to maintain a shallow water table.

PART II

EVALUATING LIQUEFACTION POTENTIAL

Liquefaction occurs in water saturated sediments during moderate to great earthquakes. Liquefied sediments are characterized by a loss of strength and may fail, causing damage to buildings, bridges, and other such structures. A number of methods for mapping liquefaction hazard have been proposed; Youd (1991) highlights the principal developments and notes some of the widely used criteria. Youd and Perkins (1978) demonstrate the use of geologic criteria as a qualitative

characterization of susceptibility units, and introduce the mapping technique of combining a liquefaction susceptibility map and a liquefaction opportunity map to evaluate liquefaction potential. Liquefaction susceptibility is a function of the capacity of sediments to resist liquefaction and liquefaction opportunity is a function of the seismic ground shaking intensity. The application of the Seed Simplified Procedure (Seed and Idriss, 1971) for evaluating liquefaction potential allows a quantitative characterization of susceptibility of geologic units. Tinsley and others (1985) applied a combination of the techniques used by Seed and others (1983) and Youd and Perkins (1978) for mapping liquefaction hazards in the Los Angeles region. The method applied in this study for evaluating liquefaction potential is similar to that of Tinsley and others (1985), combining geotechnical data analyses, and geologic and hydrologic mapping, but follows criteria adopted by the California State Mining and Geology Board (in press).

LIQUEFACTION OPPORTUNITY

According to the criteria adopted by the California State Mining and Geology Board (in press), liquefaction opportunity is a measure, expressed in probabilistic terms, of the potential for ground shaking strong enough to generate liquefaction. Analyses of in-situ liquefaction resistance require assessment of liquefaction opportunity. The minimum level of seismic excitation to be used for such purposes is the level of peak ground acceleration (PGA) with a 10% probability of exceedance over a 50-year period. The earthquake magnitude is the magnitude that contributes most to the acceleration.

For the Sunland Quadrangle, peak accelerations of 0.75 g to 0.79 g resulting from earthquakes of magnitude 6.7 to 7.0 were used for liquefaction analyses. The PGA and magnitude values were derived from maps prepared by Petersen and others (1996) and Cramer and Petersen (1996), respectively. See the ground motion portion (Section 3) of this report for further details.

LIQUEFACTION SUSCEPTIBILITY

Liquefaction susceptibility reflects the relative resistance of soils to loss of strength when subjected to ground shaking. Primarily, physical properties and conditions of soil such as sediment grain-size distribution, compaction, cementation, saturation, and depth govern the degree of resistance. Soils that lack resistance (susceptible soils) are typically saturated, loose sandy sediments. Soils resistant to liquefaction include all soil types that are dry or sufficiently dense.

DMG's map inventory of areas containing soils susceptible to liquefaction begins with evaluation of geologic maps, cross-sections, geotechnical test data, geomorphology, and ground-water hydrology. Soil-property and soil-condition factors such as type, age, texture, color, and consistency, along with historic depths to ground water are used to identify, characterize, and correlate susceptible soils. Because Quaternary geologic mapping is based on similar soil observations, findings can be related to the map units. A qualitative susceptible soil inventory is outlined below and summarized in Table 1.2.

Very old alluvium (Qvoa, Qvof1)

Very old alluvium consists is found as uplifted remnants along the front of the San Gabriel Mountains, in an area of deep ground water. On adjacent quadrangles this material is dense to very dense. Liquefaction susceptibility of this unit is low.

Old alluvium (Qof1)

Old alluvium also is generally found as raised terraces in the San Gabriel Mountains. On adjacent quadrangles this material is dense to very dense. This deposit has low liquefaction susceptibility over most of its area due to deep ground water.

Young alluvium (Qyf1, Qyf2, Qf, Qw, Qa)

Younger alluvium on the Sunland Quadrangle consists of sand with sand, silt and clay. Most boreholes in these units contain loose to moderately dense sand or silty sand. Where ground water is within 40 feet of the surface, liquefaction susceptibility of these units is high.

Quantitative Liquefaction Analysis

DMG performs quantitative analysis of geotechnical data to evaluate liquefaction potential using the Seed Simplified Procedure (Seed and Idriss, 1971; Seed and others, 1983; Seed and Harder, 1990; Youd and Idriss, 1997). This procedure calculates soil resistance to liquefaction, expressed in terms of cyclic resistance ratio (CRR) based on standard penetration test (SPT) results, ground-water level, soil density, moisture content, soil type, and sample depth. CRR values are then compared to calculated earthquake-generated shear stresses, expressed in terms of cyclic stress ratio (CSR). The factor of safety (FS) relative to liquefaction is: $FS = CRR / CSR$. FS, therefore, is a quantitative measure of liquefaction potential. Generally, a factor of safety of 1.0 or less, where CSR equals or exceeds CRR, indicates the presence of potentially liquefiable soil. DMG uses FS, as well as other considerations such as slope, free face conditions, and thickness and depth of potentially liquefiable soil, to construct liquefaction potential maps, which then directly translate to Zones of Required Investigation.

Of the about 57 borehole logs compiled for this study, only about 5 include blow-count data from SPTs or from penetration tests that allow reasonable blow count translations to SPT-equivalent values. Non-SPT values, such as those resulting from the use of 2-inch or 2 1/2-inch inside diameter ring samplers, were translated to SPT-equivalent values if reasonable factors could be used in conversion calculations. Few borehole logs, however, include all of the information (soil density, moisture content, sieve analysis, etc.) required for an ideal Seed Simplified Analysis. For boreholes having acceptable penetration tests, liquefaction analysis is performed using logged density, moisture, and sieve test values, or using average test values of similar materials.

LIQUEFACTION ZONES

Criteria for Zoning

The areas underlain by late Quaternary geologic units were included in liquefaction zones using the criteria developed by the Seismic Hazards Mapping Act Advisory Committee and adopted by the California State Mining and Geology Board (in press). Under those criteria, liquefaction zones are areas meeting one or more of the following:

1. Areas known to have experienced liquefaction during historic earthquakes.
2. All areas of uncompacted fills containing liquefaction susceptible material that are saturated, nearly saturated, or may be expected to become saturated.
3. Areas where sufficient existing geotechnical data and analyses indicate that the soils are potentially liquefiable.
4. Areas where existing geotechnical data are insufficient.

In areas of limited or no geotechnical data, susceptibility zones may be identified by geologic criteria as follows:

- a) Areas containing soil deposits of late Holocene age (current river channels and their historic floodplains, marshes and estuaries), where the M7.5-weighted peak acceleration that has a 10% probability of being exceeded in 50 years is greater than or equal to 0.10 g and the water table is less than 40 feet below the ground surface; or
- b) Areas containing soil deposits of Holocene age (less than 11,000 years), where the M7.5-weighted peak acceleration that has a 10% probability of being exceeded in 50 years is greater than or equal to 0.20 g and the historic high water table is less than or equal to 30 feet below the ground surface; or
- c) Areas containing soil deposits of latest Pleistocene age (between 11,000 years and 15,000 years), where the M7.5-weighted peak acceleration that has a 10% probability of being exceeded in 50 years is greater than or equal to 0.30 g and the historic high water table is less than or equal to 20 feet below the ground surface.

Application of SMGB criteria for liquefaction zoning in the Sunland Quadrangle is summarized below.

Areas of Past Liquefaction

Liquefaction occurred in the 1994 Northridge earthquake in the sediments behind Hansen Dam (locality 1, plate 1.2). Sand boils, fissures, and minor lateral spreading features occurred in an area about 300 by 1000 feet (Moehle, 1994). The exact location of this liquefaction is not shown in the volume by Moehle (1994), this liquefaction could have been on the San Fernando

Quadrangle or the Sunland Quadrangle, or both. Settlements of up to one foot and lateral spreading of up to three feet were reported. It is not reported if the liquefaction occurred in the recent deposits behind the dam, in the underlying Holocene wash deposits, or both.

Artificial Fills

In the Sunland Quadrangle artificial fills large enough to show at the scale of mapping include the Hansen Dam, and engineered fill for freeways. These engineered fills are generally too thin to have an impact on liquefaction hazard and so were not investigated.

Areas with Existing Geotechnical Data

Younger alluvial deposits (Qyf1, Qyf2, Qf, Qw) of the alluvial fans are composed of sand and silty sand. Most wells have layers of loose to moderately dense sand or silty sand. Those sand layers generally have a factor of safety against liquefaction of less than one in the anticipated earthquake shaking. All younger alluvial fan deposits and stream channel deposits where ground water has been less than 40 feet from the surface have been included in the liquefaction zones.

Areas without Existing Geotechnical Data

Very old alluvium and older alluvium in the Sunland Quadrangle are generally found in uplifted areas that have deep ground water. Because of the projected deep ground water and assumed dense consistency of these materials, these geologic units have not been included in liquefaction zones in this area.

ACKNOWLEDGMENTS

The author would like to thank the staff at the California Department of Transportation (Caltrans), and the Los Angeles Regional Water Quality Control Board for their assistance in the collection of subsurface borehole data. At DMG, special thanks go to Bob Moskovitz, Teri McGuire, and Scott Shepherd for their GIS operations support, and to Barbara Wanish for designing and plotting the graphic displays associated with the liquefaction zone map and this report.

REFERENCES

- Barrows, A.G., Kahle, J.E., Saul, R.B. and Weber, F.H. Jr., 1975, Geologic Map of the San Fernando earthquake area, *in* Oakeshott, G.B., *editor*, San Fernando Earthquake of 9 February, 1971: California Division of Mines and Geology Bulletin 196, plate 2, scale 1:18,000.
- Blevins, M.L., 1995, Watermaster Service in the Upper Los Angeles River Area, Los Angeles County, 1993-1994 water year: Upper Los Angeles River Area Watermaster, 45 p.

- California State Mining and Geology Board, 1997, Guidelines for evaluating and mitigating seismic hazards in California: California Department of Conservation, Division of Mines and Geology, Special Publication 117, 74 p.
- California State Mining and Geology Board, in press, Criteria for delineating seismic hazard zones: California Department of Conservation, Division of Mines and Geology, Special Publication 118, 21 p.
- California State Water Rights Board, 1962, Report of Referee, in the Superior Court of the State of California in and for the County of Los Angeles, The City of Los Angeles, a Municipal Corporation, Plaintiff, Vs City of San Fernando, a Municipal Corporation, et al, Defendants, No. 650079, volume 1, 258 p.
- Cramer, C.H. and Petersen, M.D., 1996, Predominant seismic source distance and magnitude maps for Los Angeles, Orange, and Ventura counties, California: Bulletin of Seismological Society of America, v. 86, no. 5, p. 1,645-1,649.
- Davis C.A. and Bardet, J.P., 1996, Performance of two reservoirs during 1994 Northridge earthquake: Journal of Geotechnical Engineering, v. 122, no. 8, p. 613-622.
- Dibblee, T.W., Jr., 1991, Geologic map of the Sunland and Burbank (North 1/2) quadrangles, Los Angeles County, California: Dibblee Geological Foundation Map DF-32, Santa Barbara California, map scale 1:24,000.
- Hitchcock, C.S. and Wills, C.J., 1998, Quaternary geologic mapping and seismic hazards of San Fernando Valley, California: Geological Society of America Abstracts with Programs, Cordilleran Section Meeting, Long Beach, California, v. 30, no. 5, p. 20.
- Moehle, J.P., *editor*, 1994, Preliminary report on the seismological and engineering aspects of the January 17, 1994 Northridge earthquake: University of California, Berkeley, Earthquake Engineering Research Center Report UCB/EERC-94-01.
- Morton, D.M. and Kennedy, M.P., 1989, A southern California digital 1:100,000-scale geologic map series: The Santa Ana Quadrangle, The first release: Geological Society of America Abstracts with Programs v. 21, no. 6, p. A107-A108.
- Petersen, M.D., Cramer, C.H., Bryant, W.A., Reichle, M.S. and Topozada, T.R., 1996, Preliminary seismic hazard assessment for Los Angeles, Ventura, and Orange counties, affected by the 17 January 1994 Northridge earthquake: Bulletin of the Seismological Society of America, v. 86, no. 1B, p. S247-S261.
- Seed, H.B. and Idriss, I.M., 1971, Simplified procedure for evaluating soil liquefaction potential: Journal of the Soil Mechanics and Foundations Division of ASCE, v. 97: SM9, p. 1,249-1,273.
- Seed, H.B., Idriss, I.M. and Arango, Ignacio, 1983, Evaluation of liquefaction potential using field performance data: Journal of Geotechnical Engineering, v. 109, no. 3, p. 458-482.
- Seed, H.B. and Lee, K.L., 1973, Slides in the San Fernando Dams, *in* Murphy, L. M., *editor*, San Fernando, California, Earthquake of February 9, 1971: National Oceanic and Atmospheric Administration, Washington D.C., v. 1, p. 809-813.

- Seed, R.B. and Harder, L.F., 1990, SPT-based analysis of cyclic pore pressure generation and undrained residual strength: Proceedings of the H. Bolton Seed Memorial Symposium, v. 2, p. 351-376.
- Smith, T.C., 1996, Preliminary maps of seismic hazard zones and draft guidelines for evaluating and mitigating seismic hazards: California Geology, v. 49, no. 6, p. 147-150.
- Tinsley, J.C. and Fumal, T.E., 1985, Mapping Quaternary sedimentary deposits for areal variations in shaking response, *in* Ziony, J.I., *editor*, Evaluating earthquake hazards in the Los Angeles Region -- An earth-science perspective: U.S. Geological Survey Professional Paper 1360, p. 101-125.
- Tinsley, J.C., Youd, T.L., Perkins, D.M. and Chen, A.T.F., 1985, Evaluating liquefaction potential, *in* Ziony, J.I. *editor*, Evaluating earthquake hazards in the Los Angeles region -- An earth science perspective: U.S. Geological Survey Professional Paper 1360, p 263-316.
- Wills, C.J. and Silva, Walter, 1998, Shear wave velocity characteristics of geologic units in California: Earthquake Spectra, v. 14, p. 533-556.
- Yerkes, R.F., 1996, Preliminary geologic map of the Sunland 7.5' Quadrangle, southern California: U.S. Geological Survey Open File Report 96-87. Scale 1:24,000.
- Youd, T.L., 1991, Mapping of earthquake-induced liquefaction for seismic zonation: Earthquake Engineering Research Institute, Proceedings, Fourth International Conference on Seismic Zonation, v. 1, p. 111-138.
- Youd, T.L. and Idriss, I.M., 1997, *editors*, Proceedings of the NCEER workshop on evaluation of liquefaction resistance of soils: National Center for Earthquake Engineering Research Technical Report NCEER-97-0022, 276 p.
- Youd, T.L. and Perkins, D.M. 1978, Mapping liquefaction-induced ground failure potential: Journal of Geotechnical Engineering, v. 104, p. 433-446.

SECTION 2 EARTHQUAKE-INDUCED LANDSLIDE EVALUATION REPORT

Earthquake-Induced Landslide Zones in the Sunland 7.5-Minute Quadrangle, Los Angeles County, California

**By
John P. Schlosser and Wayne Haydon**

**California Department of Conservation
Division of Mines and Geology**

PURPOSE

The Seismic Hazards Mapping Act (the Act) of 1990 (Public Resources Code, Chapter 7.8, Division 2) directs the California Department of Conservation, Division of Mines and Geology (DMG) to delineate Seismic Hazard Zones. The purpose of the Act is to reduce the threat to public health and safety and to minimize the loss of life and property by identifying and mitigating seismic hazards. Cities, counties, and state agencies are directed to use the seismic hazard zone maps in their land-use planning and permitting processes. The Act requires that site-specific geotechnical investigations be performed prior to permitting most urban development projects within the hazard zones. Evaluation and mitigation of seismic hazards are to be conducted under guidelines established by the California State Mining and Geology Board (1997; also available on the Internet at <http://www.consrv.ca.gov/pubs/sp/117/>).

This evaluation report summarizes seismic hazard zone mapping for earthquake-induced landslides in the Sunland 7.5-minute Quadrangle (scale 1:24,000). This section and Section 1 addressing liquefaction, are part of a series that will summarize development of similar hazard zone maps in the state (Smith, 1996). Additional information on seismic hazard zone mapping in California can be accessed on DMG's Internet homepage: <http://www.consrv.ca.gov/dmg/shezp/>

BACKGROUND

Landslides triggered by earthquakes have historically been a major cause of earthquake damage. Landslides triggered by the 1971 San Fernando, 1989 Loma Prieta, and 1994 Northridge earthquakes were responsible for destroying or damaging numerous homes and other structures, blocking major transportation corridors, and damaging various types of lifeline infrastructure. Typically, areas most susceptible to earthquake-induced landslides are steep slopes and on or adjacent to existing landslide deposits, especially if the earth materials in these areas are composed of loose colluvial soils, or poorly cemented or highly fractured rock. These geologic and terrain conditions exist in many parts of southern California, most notably in hilly areas already developed or currently undergoing development. In addition, the opportunity for strong earthquake ground shaking is high because of many nearby active faults. The combination of these factors constitutes a significant seismic hazard in the southern California region, which includes the Sunland Quadrangle.

SCOPE AND LIMITATIONS

The methodology used to make this map is based on earthquake ground-shaking estimates, geologic material-strength characteristics and slope gradient. These data are gathered primarily from a variety of outside sources; thus the quality of the data is variable. Although selection of data used in this evaluation was rigorous, the state of California and the Department of Conservation make no representations or warranties regarding the accuracy of the data gathered from outside sources.

Earthquake-induced landslide zone maps are intended to prompt more detailed, site-specific geotechnical investigations as required by the Act. As such, these zone maps identify areas where the potential for earthquake-induced landslides is relatively high. Earthquake-generated ground failures that are not addressed by this map include those associated with ridge-top spreading and shattered ridges. No attempt has been made to map potential run-out areas of triggered landslides. It is possible that such run-out areas may extend beyond the zone boundaries. The potential for ground failure resulting from liquefaction-induced lateral spreading of alluvial materials, considered by some to be a form of landsliding, is not specifically addressed by the earthquake-induced landslide zone or this report. See Section 1, Liquefaction Evaluation Report for the Sunland Quadrangle for more information on the delineation of Liquefaction Zones.

Information developed in the study is presented in two parts: physiographic and geologic conditions in PART I, and ground shaking opportunity, landslide susceptibility and zoning evaluations in PART II.

PART I

STUDY AREA LOCATION AND PHYSIOGRAPHY

The Sunland Quadrangle covers an area of about 62 square miles in western Los Angeles County. The community of Sunland, which is about 14 miles north-northwest of the Los Angeles Civic Center, and the adjacent community of Tujunga, both parts of the City of Los Angeles, are scattered across the northern San Fernando Valley floor in the southern part of the quadrangle. North of the San Fernando Valley, the San Gabriel Mountains cover about four-fifths of the Sunland Quadrangle. Except for a small fringe of unincorporated Los Angeles County land along the mountain front most of the land in the mountains lies within the Angeles National Forest. South of Tujunga Valley, the northwestern end of the Verdugo Mountains extends into the southern edge of the quadrangle. Canyons within the mountains extend south to the San Fernando Valley.

The San Fernando Valley is an east-trending structural trough within the Transverse Ranges of southern California. The San Gabriel Mountains that bound it to the northeast are composed of plutonic and metamorphic rocks that are being thrust over the valley from the north. As the range has been elevated and deformed, the San Fernando Valley has subsided and filled with sediment.

The northern portion of the San Fernando Valley in the Sunland Quadrangle has received sediment from drainage systems originating in the San Gabriel Mountains. The larger systems, Little Tujunga and Big Tujunga washes, are large river systems that have their sources in the steep, rugged San Gabriel Mountains. Each of these drainage systems has a drainage basin of tens of square miles within the mountains and can carry a large volume of sediment. The alluvial fans deposited by these drainage systems have their apexes outside of the Sunland Quadrangle in the southern San Fernando Quadrangle and cover most of the Van Nuys and Burbank quadrangles to the south. Composition of these deposits is dependent on the source areas of the drainages. Drainages with source areas in the San Gabriel Mountains primarily have granitic or other plutonic rocks in their drainage basins. The deposits of these streams consequently are composed of sandy alluvium.

The Seismic Hazard Zone Map for the this quadrangle has been trimmed back so that it covers essentially only the south half of the Sunland 7.5-minute Quadrangle. The northern boundary of the zone map is located 1.5 to 2.5 miles north of the Angeles National Forest Boundary along the San Gabriel Mountain front. The land excluded from the zone map is almost entirely National Forest land with only a few scattered inholdings of private property.

GEOLOGIC CONDITIONS

Surface and Bedrock Geology

For the Sunland Quadrangle, a recently compiled geologic map was obtained from the U.S. Geological Survey (USGS) in digital form (Yerkes, 1996). Other geologic maps reviewed for this project include: Oakeshott (1958), Barrows and others, (1975), Weber (1982), Crook and others

(1987) and Dibblee (1991). The digital geologic map was modified to reflect the most recent mapping in the area and to include interpretations of observations made during the aerial photograph landslide inventory and field reconnaissance. Modifications to the geologic map included remapping most of the contacts between the bedrock and Quaternary units. In the field, observations were also made of exposures, aspects of weathering, and general surface expression of the geologic units. In addition, the relation of the various geologic units to development and abundance of slope failures was noted.

The uplands of the Sunland Quadrangle are underlain by Precambrian to Mesozoic igneous and metamorphic rocks that are faulted against or overlain by Paleocene to Pleistocene sedimentary and volcanic rocks, and Holocene alluvium. The northwest-striking San Gabriel Fault crosses the northern half of the quadrangle and separates contrasting geologic terranes. This fault generally, but not entirely, separates the Precambrian metamorphic rocks exposed northeast of the fault from the younger igneous, metamorphic and sedimentary rocks exposed southwest of the fault. The oldest rocks in the Sunland Quadrangle are Precambrian Mendenhall Gneiss (pCm) and anorthosite complex rocks (an) exposed north of the San Gabriel Fault. The Mendenhall Gneiss consists of blue quartz-plagioclase gneiss intruded by rocks of the anorthosite complex that are composed of medium to very coarse-grained, pale gray to white plagioclase and, in the gabbroic phases, pyroxene that weathers to a dark grayish green. The anorthosite complex includes abundant varieties of gabbroic rocks (gb), especially norite and inclusion of ilmenite-magnetite gabbro (gbm).

An assortment of pre-Cenozoic igneous and metamorphic rocks are exposed south of the San Gabriel Fault. The oldest of these rocks is the pre-Triassic? Placerita Formation (pm), which consists of biotite-quartz-feldspar gneiss, meta-quartzite, biotite schist-gneiss, and small bodies of marble, limestone, and dolomite. Mesozoic diorite gneiss (dgn) is the next youngest unit consisting of dark gneiss, meta-diorite, hornblende diorite and local amphibole schist. The youngest of the Mesozoic rocks is the granodiorite (gd) unit, which is comprised of medium- to coarse-grained granitic rocks that range from quartz diorite to granite that is locally gneissic near contacts with the older rocks. The igneous and metamorphic rocks, which form the basement rocks in the study area, are exposed along the north half of the western, northern, the entire eastern and about the central third of the southern boundaries of the study area, and outcrop over more than three-fourths of the upland terrain in the Sunland Quadrangle.

Sedimentary rocks that rest upon the basement south of the San Gabriel Fault are identified in the southwestern quarter and the western half of the southeastern quarter of the quadrangle. These rocks form generally northwest-trending bands that underlie the foothills north of the San Fernando Fault and the northwestern end of the Verdugo Mountains. The oldest of this sequence of sedimentary rocks is the Paleocene Martinez Formation (Tmz) of Yerkes (1996) and Oakeshott (1958), and mapped as the Santa Susana Formation by Dibblee (1991). It consists of marine sandstone, thin interbeds of black shale and lenticular beds of pebble conglomerate. These rocks are only exposed in slivers along the south side of the San Gabriel Fault.

The middle Miocene Topanga Formation (Tt) is exposed south of Tujunga Valley, south and east of Sunland Boulevard. This formation consists of nonmarine arkose and conglomerate, as well as

vesicular basaltic flows and minor breccia (Tb). The Modelo Formation (Tm) rests conformably upon Topanga Formation south of Tujunga Valley, north and west of Sunland Boulevard and lies directly north of the San Fernando Fault. The Modelo consists of upper Miocene diatomaceous to cherty shale, sandstone, and conglomerate. The Pico Formation (Tp), also mapped as Towsley (?) Formation by Dibblee (1991), consists of upper Pliocene sandstone and pebble conglomerate that conformably overlies the Modelo Formation.

The youngest lithified sedimentary unit is the Plio-Pleistocene nonmarine Saugus Formation (Qs). The Saugus Formation has a larger outcrop area in the quadrangle than any other sedimentary unit. The Saugus Formation is exposed in the center of the western half of the quadrangle where it either rests unconformably upon Pico Formation or igneous and metamorphic rocks or is in fault contact with Modelo Formation or igneous and metamorphic rocks. The Saugus Formation consists of nonmarine pebble conglomerate and coarse-grained arkosic sandstone.

The late Quaternary geologic units exposed on geomorphic terraces in the uplands and exposed on the uplifted and undeformed portions of the flatlands in the San Fernando Valley area of the Sunland Quadrangle were completely re-mapped for this study. The geomorphic terraces and the uplifted flatlands in the San Fernando Valley area were mapped as a variety of alluvial units including: older and very old alluvium (Qof1, Qoal, Qvoa, Qvof, Qvof1, and Qao), terrace deposits (Qt), and alluvium-breccia deposits (Qab). These alluvial units consist of moderately dense to very dense sand, clayey and silty sand, gravel and clay layers. The undeformed portions of the flatlands in the San Fernando Valley area are underlain by younger alluvium (Qal, Qya1, Qyf1, Qyf2, and Qw), which consists of loose, moderately dense sand, silty sand, gravelly sand and minor clay. A more detailed description of the late Quaternary geologic units is presented in the Liquefaction portion (Section 1) of this report.

Landslide deposits (Qls) are relatively abundant south of the San Gabriel Fault and north of the Tujunga Valley in the west-central portion of the quadrangle where they occur on the sedimentary and igneous rocks of the uplands. Landslides in the sedimentary rocks were identified primarily on the Saugus Formation and Modelo Formation, where they occur individually or as landslide complexes, and range in size from small to large. Landslides in the igneous rocks occur primarily in the granodiorite and form complexes along the Lopez Fault (Dibblee, 1991; Treiman, unpublished) or are otherwise scattered throughout the outcrop area of the basement complex. The landslides in the granodiorite range in size from small to large, with most of the largest single landslides and landslide complexes along the Lopez Fault to the northwest of Little Tujunga Canyon. The scattered landslides in the granodiorite also range in size from small to large, but most are small with fewer large landslides than in the sedimentary rocks.

Modern man-made fill (af), and cut/fill (acf) occur primarily along freeway embankments. A more detailed description of the man-made fill is presented in Section 1 of this report.

Geologic Material Strength

To evaluate the stability of geological materials under earthquake conditions, they first must be ranked on the basis of their overall shear strength. Generally, the primary source for rock shear-

strength measurements is geotechnical reports prepared by consultants on file with local government permitting departments. Shear strength data for the rock units identified on the geologic map were obtained from the City of Los Angeles, Department of Public Works (see Appendix A). Due to land-ownership patterns within the quadrangle, residential and commercial development has taken place primarily on the gently sloping alluvial areas of the San Fernando Valley, and on the hills at the north end of the Verdugo Mountains. Consequently, shear strength information was scarce or entirely lacking for many rock units in the San Gabriel Mountain portion of the quadrangle. Where appropriate, strength data from rock units in adjacent quadrangles were used to characterize the shear strength of rock units within the Sunland Quadrangle. The use of the data was considered appropriate where the rock units were similar in lithology, in fairly close proximity (within a few miles of the Sunland Quadrangle), and where generally along the same strike as the rock units within the Sunland Quadrangle. One shear test report from the Burbank Quadrangle just south of the Sunland Quadrangle, and 4 shear test reports from the San Fernando Quadrangle were used to help characterize the Topanga Formation in the Sunland Quadrangle.

The locations of rock and soil samples taken for shear testing, within the Sunland Quadrangle and immediately south in the Burbank Quadrangle, are shown on Plate 2.1. The four samples taken in the San Fernando Quadrangle are shown in the evaluation report for that quadrangle.

Shear strength data gathered from the above sources were compiled for each mapped geologic unit, and subdivided for fine-grained and coarse-grained lithologies, if appropriate. Geologic units were grouped on the basis of average angle of internal friction (average f) and lithologic character. Geologic formations that had little or no shear test information were added to existing groups on the basis of lithologic and stratigraphic similarities.

The crystalline rocks of the San Gabriel Mountains, as a group, have engineering characteristics different from other rock units in the quadrangle, yet very few shear test results were available for them from the quadrangle, or from adjacent quadrangles. Thus some assumptions had to be made about the choice of ϕ value for the rock group, based on field observations and comparisons with other rock units. The ancient crystalline bedrock in the western San Gabriel Mountains is pervasively fractured. This pervasive fracturing is the dominant physical characteristic of all the crystalline rocks, and it appears to dominate the engineering behavior of the rocks, regardless of their mineralogy, age, or metamorphic history. Although they are pervasively fractured, the rocks support some of the steepest slopes in the quadrangle, and are, therefore, likely to be some of the strongest rocks in the quadrangle. For the purpose of slope stability analysis, all the crystalline rocks of the San Gabriel Mountains and Verdugo Mountains were consolidated into one group (Kgr), and this group was designated as the highest strength group. A ϕ value of 38 degrees was chosen to represent the group, based on ϕ values published in rock mechanics and engineering geology text books (Franklin and Dusseault, 1989; Hoek and Bray, 1981; and Jumikis, 1983) and comparison with shear test results for the group. The value of 38 degrees was in the middle of the range of the few shear test results that were collected from the quadrangle and the surrounding area.

Existing landslides (Qls) were assigned a ϕ of 14 for stability analysis calculations for this quadrangle. None of the geotechnical reports reviewed for the quadrangle contained any direct shear tests run on actual slide plane material, but there were a few such test results for nearby quadrangles. The ϕ values for slide plane material actually tested had a wide range, and 14 was near the low end of this range. In those geotechnical reports that provided slope stability calculations, conservative assumed ϕ values were generally chosen, and 14 was again on the low end of the range of values used.

To subdivide mapped geologic formations that have both fine-grained and coarse-grained lithologies, we assumed that where stratigraphic bedding dips into a slope (favorable bedding) the coarse-grained material strength dominates, and where bedding dips out of a slope (adverse bedding) the fine-grained material strength dominates. We then used structural information from the geologic map (see "Structural Geology") and terrain data in the form of slope gradient and aspect, to identify areas with a high potential for containing adverse bedding conditions. These areas, located on the map, were then used to modify the geologic material-strength map to reflect the anticipated lower shear strength for the fine-grained materials.

The results of the grouping of geologic materials in the quadrangle are in Tables 2.1 and 2.2.

Structural Geology

Regional faults are the primary structural features of the Sunland Quadrangle. The northwest-striking San Gabriel Fault is the dominant structure in the northern half of the Sunland Quadrangle. In the southern third of the quadrangle, however, the Lakeview Segment of the San Fernando Fault, which ruptured at the surface during the February 9, 1971 earthquake, defines the southern edge of the mountain front. Faulting along the Lakeview Segment juxtaposes Modelo Formation over coarse, older alluvium-breccia deposits. The fault also crosses the Modelo Formation and the Quaternary (modern) wash deposits at the mouths of Little Tujunga and Big Tujunga canyons. This fault is referred to as the Lakeview Fault Zone on the map by Dibblee (1991) and the Lakeview Segment of the San Fernando Fault on the map by Barrows and others (1975).

Numerous shorter faults that trend northwest-southeast or north-south are scattered throughout the uplands. Fault names used in the following discussion are taken from Dibblee (1991), and Barrows and others (1975). The De Mille Fault and Watt Fault are local strands of the San Gabriel Fault and are just south of that fault. Near the western margin of the quadrangle and just south of the San Gabriel Fault, the Buck Canyon Fault trends generally east-west and forms the contact between the Saugus Formation and the granodiorite. Farther to the southeast, an unnamed fault that trends southwest-northeast is just northwest of Kagel Canyon. The Lopez Fault is exposed just northwest of Little Tujunga Canyon where it forms the contact between the Saugus Formation and the granodiorite and diorite-gneiss. The fault forms a backward "L", with the southern portion of the fault trending west-northwest and the northern portion trending north-northeast. South of Yerba Buena Ridge, the Sunland Fault trends in an arcuate, open to the north-northeast, pattern from Little Tujunga Canyon on the west to Big Tujunga Canyon to the east.

In the igneous and metamorphic basement rocks north of the San Gabriel Fault the foliation strikes generally about northwest-southeast, parallel to the San Gabriel Fault and locally northeast-southwest. Dips of the foliation in the Mendenhall Gneiss, anorthosite complex and gabbroic rocks range between 20 and 70 degrees, generally to the southwest, but locally to the northwest or northeast. In the granodiorite south of the San Gabriel Fault the foliation strikes generally about northwest-southeast, parallel to the San Gabriel Fault with typically vertical dips, but locally, dips greater than 50 degrees are inclined toward the northeast, towards the San Gabriel Fault. Foliations in the diorite gneiss and Placerita Formation are less well defined, but generally strike about northwest-southeast, and dip typically northward 75 degrees to vertical. Bedding in the sedimentary rocks typically strikes northwest-southeast, parallel to the San Gabriel Fault, although locally, especially near the other faults, bedding strikes northeast or is overturned. Dips here are between 10 and 70 degrees.

A number of folds have been mapped in the western half of the Sunland Quadrangle. Just south of the San Gabriel Fault, a short parallel anticline and syncline trending southwest-northeast and a short syncline trending northwest-southeast were mapped in the Saugus Formation. Dips on the limbs of the folds are between 5 and 30 degrees, but locally as high as 50 degrees. The Merrick Syncline lies between the San Fernando Fault and the Lakeview Segment of the San Fernando Fault, in the Saugus Formation. The axial trace of the syncline trends northwest-southeast. The syncline is asymmetric with dips between 25 and 70 degrees to the north on the southern limb, and between 50 degrees to the south to an overturned 75 degrees to the northeast on the northern limb. Exposed in the hills south of Tujunga Valley are an alternating set of two anticlines and two synclines that trend nearly east-west. Dips of the folded Modelo Formation strata are typically between 5 and 20 degrees but locally are up to 30 degrees.

Accompanying the digital geologic map (Yerkes, 1996) were digital files of associated geologic structural data, including bedding and foliation attitudes (strike and dip) and fold axes. We used the structural geologic information provided with the digital geologic map (Yerkes, 1996) and from Dibblee's geologic map of Sunland Quadrangle (Dibblee, 1991) to categorize areas of common stratigraphic dip direction and magnitude, similar to the method presented by Brabb (1983). The dip direction category was compared to the slope aspect (direction) category and, if the same, the dip magnitude and slope gradient categories were compared. If the dip magnitude category was less than or equal to the slope gradient category, and the bedding dip was greater than 25% (4:1 slope), the area was marked as a potential adverse bedding area. This information was then used to subdivide mapped geologic units into areas where fine-grained and coarse-grained strengths would be used.

Landslide Inventory

The evaluation of earthquake-induced landsliding requires an up-to-date and complete picture of the previous occurrence of landsliding. An inventory of the existing landslides in the entire

SUNLAND QUADRANGLE SHEAR STRENGTH STATISTICS

	Formation Name	Number of Tests	Mean/Median Phi (deg)	Mean/Median Group Phi (deg)	Mean/Median Group C (psf)	No Data: Similar Lithology	Phi Values Used in Stability Analysis
GROUP 1	Kgr*	0				Kgr*	38
GROUP 2	Tm-fbc Qa* Ttc-fbc Tp-fbc	20 24 18 5	33.9/35 33.5/33 33.8/33 33.6/35	34.6/34	362/300	Td, Tcs-fbc Tmc1-fbc, Tvz-fbc Tb	35
GROUP 3	Tm-abc Tp-abc	17 6	27.8/29 28.2/27	29.6/30	348/255	Tmc2-fbc	30
GROUP 4	Ttc-abc	7	24.7/25	24.7/26	757/490	Tcs-abc, Tmc1-abc	26
GROUP 5	Qls	0		14	400	Qls*	14**

abc = adverse bedding condition, fine-grained material strength

fbc = favorable bedding condition, coarse grained material strength

Kgr* = pre-Tertiary crystalline units

Qa* = af (fill) and Quaternary units

* = subunits of these formations have been combined

** = lowest calculated phi value was accepted as representative phi value for landslides

Table 2.1. Summary of the shear strength statistics for the Sunland Quadrangle.

SHEAR STRENGTH GROUPS FOR THE SUNLAND QUADRANGLE

GROUP 1	GROUP 2	GROUP 3	GROUP 4	GROUP 5
An dgn gb gbm gd pCm pm	Tm-fbc Ttc-fbc Tp-fbc Tb Qs-fbc af & acf Qab Qal Qao Qao1 Qof1 Qt Qvoa Qvof & Qvof1 Qw	Tm-abc Tp-abc Qs-abc	Ttc-abc Tmz	Qls

Table 2.2. Summary of the shear strength groups for the Sunland Quadrangle.

Sunland Quadrangle was prepared using interpretation of stereo-paired aerial photographs of the study area and limited field reconnaissance (Treiman, unpublished). All areas containing

landslides identified in the previous work of: Oakeshott (1958); Morton and Streitz (1969); Morton\ (1975); Weber (1982); and Dibblee (1991) where re-evaluated during the aerial photograph interpretation conducted for this investigation. Some of the landslides identified in the previous work were not included in the landslide inventory because in our reevaluation, it was concluded the feature was not a landslide. Many additional landslides were identified, and the boundaries of many of the landslides identified in the previous work were modified. Additionally, all landslides shown on the digital geologic map (Yerkes, 1996) were verified, re-mapped or removed during preparation of the inventory maps. The completed hand-drawn landslide map was scanned, digitized and the database was attributed with landslide information on confidence of interpretation (definite, probable, or questionable) and other properties, such as activity, thickness, and associated geologic unit(s). To keep the landslide inventories of consistent quality, all landslides originally depicted on the digitized geologic map were deleted and only those included in the DMG inventory were incorporated into the hazard-evaluation process. A version of this landslide inventory is included with Plate 2.1.

PART II

EARTHQUAKE-INDUCED LANDSLIDE GROUND SHAKING OPPORTUNITY

Design Strong-Motion Record

The Newmark analysis used in delineating the earthquake-induced landslide zones requires the selection of a design earthquake strong-motion record. For the Sunland Quadrangle, the selection was based on an estimation of probabilistic ground motion parameters for modal magnitude, modal distance, and peak ground acceleration (PGA). The parameters were estimated from maps prepared by DMG for a 10% probability of being exceeded in 50 years (Petersen and others, 1996; Cramer and Petersen, 1996). The parameters used in the record selection are:

Modal Magnitude:	6.8 to 7.6
Modal Distance:	2.6 to 16.6 km
PGA:	0.55 to 0.77 g

The strong-motion record selected was the Channel 3 (north horizontal component) Pacoima-Kagel Canyon Fire Station recording from the magnitude 6.7 Northridge earthquake (Shakal and others, 1994). This record had a source to recording site distance of 2.6 km and a PGA of 0.44 g. The selected strong-motion record was not scaled or otherwise modified prior to analysis.

Displacement Calculation

To develop a relationship between the yield acceleration (a_y ; defined as the horizontal ground acceleration required to cause the factor of safety to equal 1.0) and Newmark displacements, the design strong-motion record was integrated twice for a given a_y to find the corresponding displacement, and the process repeated for a range of a_y (Jibson, 1993). The resulting curve in

Figure 2.1 represents the full spectrum of displacements that can be expected for any combination of geologic material strength and slope angle, as represented by the yield acceleration. We used displacements of 30, 15 and 5 cm as criteria for rating levels of earthquake shaking damage on the basis of the work of Youd (1980), Wilson and Keefer (1983), and the DMG pilot study for earthquake-induced landslides (McCrink and Real, 1996). Applied to the curve in Figure 2.1, these displacements correspond to yield accelerations of 0.074, 0.13 and 0.21 g. Because these yield acceleration values are derived from the design strong-motion record, they represent the ground shaking opportunity thresholds that are significant to the Sunland Quadrangle.

EARTHQUAKE-INDUCED LANDSLIDE HAZARD POTENTIAL

Terrain Data

The calculation of slope gradient is an essential part of the evaluation of slope stability under earthquake conditions. To calculate slope gradient for the terrain within the Sunland Quadrangle, a Level 2 digital elevation model (DEM) was obtained from the USGS (U.S. Geological Survey, 1993). This DEM, which was prepared from the 7.5-minute quadrangle contours, has a 10-meter horizontal resolution and a 7.5-meter vertical accuracy. Surrounding quadrangle DEMs were merged with the Sunland DEM to avoid the loss of data at the quadrangle edges when the slope calculations were performed. A peak and pit smoothing process was then performed to remove errors in the elevation points.

To update the topographic base map, areas that have undergone large-scale grading as a part of residential development or freeway construction in the hilly portions of the Sunland Quadrangle, along the base of the San Gabriel Mountains and at the north end of the Verdugo Mountains were identified on aerial photography flown in the spring of 1994 (see Plate 2.1). Terrain data for these areas were obtained from an airborne interferometric radar (TOPSAR) DEM flown and processed in August 1994 by NASA's Jet Propulsion Laboratory (JPL), and reprocessed by Calgis, Inc. (GeoSAR Consortium, 1995 and 1996). These terrain data were also smoothed prior to analysis.

Slope-gradient and aspect maps were made from the DEMs using a third-order, finite difference, center-weighted algorithm (Horn, 1981). The slope-gradient maps were used first in conjunction with the aspect maps and geologic structural data to identify areas of potential adverse bedding conditions, and then again with the geologic strength map in preparation of the earthquake-induced landslide hazard potential map.

Stability Analysis

A slope stability analysis was performed for each geologic material strength group at slope increments of 1 degree. An infinite-slope failure model under unsaturated slope conditions was assumed. A factor of safety was calculated first, followed by the calculation of yield acceleration from Newmark's equation:




Figure 2.1. Yield acceleration vs. Newmark displacement for the Pacoima-Kagel Canyon strong-motion record From the 17 January 1994 Northridge, California Earthquake. Record from California Strong Motion Instrumentation Program (CSMIP) Station 24088.

$$a_y = (FS - 1)g \sin \alpha$$

where FS is the Factor of Safety, g is the acceleration due to gravity, and α is the direction of movement of the slide mass, in degrees measured from the horizontal, when displacement is initiated (Newmark, 1965). For an infinite slope failure α is the same as the slope angle.

The yield acceleration calculated by Newmark's equations represents the susceptibility to earthquake-induced failure of each geologic material strength group for a range of slope gradients. The acceleration values were compared with the ground shaking opportunity, defined by Figure 2.1, to determine the earthquake-induced landslide hazard potential. Based on the criteria described in Figure 2.1 above, if the calculated yield acceleration was less than 0.074g, expected displacements could be greater than 30cm, and a HIGH (H on Table 2.3) hazard

potential was assigned. Likewise, if the calculated a_y fell between 0.074 and 0.13g a MODERATE (M on Table 2.3) hazard potential was assigned, between 0.13 and 0.21g a LOW (L on Table 2.3) potential was assigned, and if a_y were greater than 0.21g a VERY LOW (VL on Table 2.3) potential was assigned.

Table 2.3 summarizes the results of the stability analyses. The earthquake-induced landslide hazard potential map was prepared by combining the geologic material-strength map and the slope map according to this table.

SUNLAND QUADRANGLE HAZARD POTENTIAL MATRIX

		SLOPE CATEGORY										
Geologic Material Group	Mean Phi	I 0-11%	II 11-18%	III 18-25%	IV 25-34%	V 35-40%	VI 40-44%	VII 44-48%	VIII 48-59%	IX 59-69%	X 69-74%	XI >74%
1	38	VL	VL	VL	VL	VL	VL	VL	VL	L	M	H
2	34	VL	VL	VL	VL	VL	VL	L	M	H	H	H
3	29	VL	VL	VL	VL	L	M	M	H	H	H	H
4	25	VL	VL	VL	L	M	H	H	H	H	H	H
5	14	L	M	H	H	H	H	H	H	H	H	H

Table 2.3. Hazard potential matrix for earthquake-induced landslides in the Sunland Quadrangle. Shaded area indicates hazard potential levels included within the hazard zone.

EARTHQUAKE-INDUCED LANDSLIDE ZONE

Criteria for Zoning

Earthquake-induced landslide zones were delineated using criteria adopted by the California State Mining and Geology Board (in press). Under those criteria, earthquake-induced landslide zones are areas meeting one or more of the following:

1. Areas known to have experienced earthquake-induced slope failure during historic earthquakes.
2. Areas identified as having past landslide movement, including both landslide deposits and source areas.

3. Areas where CDMG's analyses of geologic and geotechnical data indicate that the geologic materials are susceptible to earthquake-induced slope failure.

Existing Landslides

Studies of the types of landslides caused by earthquakes (Keefer, 1984) show that re-activation of the whole mass of deep-seated landslide deposits is rare. However, it has been observed that the steep scarps and toe areas of existing landslides, which formed as a result of previous landslide movement, are particularly susceptible to earthquake-induced slope failure. In addition, because they have been disrupted during landslide movement, landslide deposits are inferred to be weaker than coherent, undisturbed, adjacent source rocks. Finally, we felt that a long duration, San Andreas fault-type earthquake could be capable of initiating renewed movement in existing deep-seated landslide deposits. Therefore, all existing landslides identified in the inventory with a definite or probable confidence of interpretation were included in the hazard zone.

The February 9, 1971 San Fernando earthquake triggered widespread rockfalls, soil falls, debris slides, avalanches, and slumps in the foothills of the San Gabriel Mountains that rise above the Lakeview segment of the San Fernando Fault (Morton, 1975). Most of the failures were shallow debris or soil falls, although the largest landslide triggered by the San Fernando earthquake, a reactivated slump on the east side of Schwartz Canyon, also occurred within the Sunland Quadrangle (Morton, 1975, plate 3). Along the stretch of the Lakeview segment of the San Fernando Fault between Little Tujunga and Big Tujunga canyons a series of nearly continuous landslides resulted from an unusual mechanism described by Kahle (1975, p. 129). The combination of shaking and oversteepening due to overthrusting of upper plate material upward and southward towards the valley generated the thin soil falls along the fault trace.

The 1994 Northridge earthquake caused a number of relatively small, shallow slope failures in the Sunland Quadrangle (Harp and Jibson, 1995), although they were neither as widely distributed nor as abundant as those triggered by the 1971 event.

Geologic and Geotechnical Analysis

On the basis of a DMG pilot study (McCrink and Real, 1996) the earthquake-induced landslide zone includes all areas determined to lie within the High, Moderate and Low levels of hazard potential. Therefore, as shown in Table 2.3, geologic strength group 5 is always included in the zone (mapped landslides); strength group 4 materials are included in the zone for all slope gradients above 25%; strength group 3 above 34%; strength group 2 above 44%; and strength group 1 materials, the strongest rock types, are zoned for slope gradients above 59%. This results in roughly 22% of the land in the quadrangle, including National Forest Service land, lying within the hazard zone.

ACKNOWLEDGMENTS

The authors would like to thank the following individuals and organizations for their assistance in obtaining the data necessary to complete this project. Geologic material strength data were collected at the City of Los Angeles with the assistance of Nicki Girmay. Digital terrain data were provided by Randy Jibson of the U.S. Geological Survey (USGS DEM), Scott Hensley of JPL and Gerald Dildine and Chris Bohain of Calgis, Inc. (Radar DEM). Technical review of the methodology was provided by Bruce Clark, Randy Jibson, Robert Larson, Scott Lindvall, and J. David Rogers, who are members of the State Mining and Geology Board's Seismic Hazards Mapping Act Advisory Committee Landslides Working Group. At DMG, special thanks to Bob Moskovitz, Teri McGuire, Barbara Wanish, and Scott Shepherd for their GIS operations support, and to Barbara Wanish for designing and plotting the graphic displays associated with the Hazard Zone Map and this report.

REFERENCES

- Barrows, A.G., Kahle, J.E., Saul, R.B. and Weber, F.H. Jr., 1975, Geologic Map of the San Fernando earthquake area, *in* Oakeshott, G.B., *editor*, San Fernando Earthquake of 9 February, 1971: California Division of Mines and Geology Bulletin 196, plate 2, scale 1:18,000.
- Brabb, E.E., 1983, Map showing direction and amount of bedding dip of sedimentary rocks in San Mateo County, California: U.S. Geological Survey Miscellaneous Investigations Series Map I-1257C, 1 sheet, scale 1:62,500.
- California State Mining and Geology Board, 1997, Guidelines for evaluating and mitigating seismic hazards in California: California Department of Conservation, Division of Mines and Geology, Special Publication 117, 74 p.
- California State Mining and Geology Board, in press, Criteria for delineating seismic hazard zones: California Department of Conservation, Division of Mines and Geology, Special Publication 118, 21 p.
- Cramer, C.H. and Petersen, M.D., 1996, Predominant seismic source distance and magnitude maps for Los Angeles, Orange and Ventura counties, California: Bulletin of the Seismological Society of America, v. 85, no. 5, p. 1645-1649.
- Crook, R., Jr., Allen, C.R., Kamb, B., Payne, C.M. and Proctor, R.J., 1987, Quaternary geology and seismic hazard of the Sierra Madre and associated faults, Western San Gabriel Mountains: U.S. Geological Survey Professional Paper 1339, Chapter 2, p.27-64. map scale 1:24,000.
- Dibblee, T.W., Jr., 1991, Geologic map of the Sunland and Burbank (North 1/2) quadrangles, Los Angeles County, California: Dibblee Geological Foundation Map DF-32, Santa Barbara California, scale 1:24,000.
- Franklin, J.A. and Dusseault, M.B., 1989, Rock Engineering: McGraw-Hill Publishing Company.

- GeoSAR Consortium, 1995, Year 1: Research and development status report for GeoSAR, a radar-based terrain mapping project: U.S. Government's Advanced Research Projects Agency Contract Order No. B335/00, 135 p.
- GeoSAR Consortium, 1996, Year 2: Research and development status report for GeoSAR, a radar-based terrain mapping project: U.S. Government's Advanced Research Projects Agency Contract Order No. B378/00, 70 p.
- Harp, E.L. and Jibson, R.W., 1995, Landslides triggered by the January 17, 1994 Northridge, California earthquake: U.S. Geological Survey Open-File Report 95-213, 17 p., Plate 1 scale 1:100,00; Plate 2 scale 1:50,000.
- Horn, B.K.P., 1981, Hill shading and the reflectance map: *Proceedings of the IEEE*, v. 69, no. 1, p. 14-47.
- Hoek, E. and Bray, J., 1981, *Rock Slope Engineering*, 3rd Edition: The Institution of Mining and Metallurgy, London.
- Jibson, R.W., 1993, Predicting earthquake-induced landslide displacements using Newmark's sliding block analysis: Transportation Research Board, National Research Council, Transportation Research Record 1411, 17 p.
- Jumikis, A.R. 1983, *Rock Mechanics*, Second Edition: Trans Tech Publications
- Kahle, J.E., 1975, Surface effects and related geology of the Lakeview fault segment of the San Fernando Fault Zone, *in* Oakeshott, G.B., *editor*, San Fernando Earthquake of 9 February, 1971: California Division of Mines and Geology Bulletin 196, p. 119-135.
- Keefer, D.K., 1984, Landslides caused by earthquakes: *Geological Society of America Bulletin*, v. 95, no. 4, p. 406-421.
- McCrink, T.P. and Real, C.R., 1996, Evaluation of the Newmark method for mapping earthquake-induced landslide hazards in the Laurel 7-1/2 minute Quadrangle, Santa Cruz County, California: California Division of Mines and Geology Final Technical Report for U.S. Geological Survey Contract 143-93-G-2334, U.S. Geological Survey, Reston Virginia, 31 p.
- Morton, D. M., 1975, Seismically triggered landslides in the area above the San Fernando Valley, *in* Oakeshott, G.B., *editor*, San Fernando Earthquake of 9 February, 1971: California Division of Mines and Geology Bulletin 196, p. 145-154, plate 3, scale 1:24,000.
- Morton, D.M. and Streitz, Robert, 1969, Preliminary reconnaissance map of major landslides, San Gabriel Mountains, California: California Division of Mines and Geology, Map Sheet 15, scale 1:62,500.
- Newmark, N.M., 1965, Effects of earthquakes on dams and embankments: *Geotechnique*, v. 15, no. 2, p. 139-160.
- Oakeshott, G.B., 1958, Geology and mineral resources of San Fernando Quadrangle, Los Angeles County, California: California Division of Mines and Geology Bulletin 172, 147 p., map scale 1:62,500.

- Petersen, M.D., Cramer, C.H., Bryant, W.A., Reichle, M.S. and Topozada, T.R., 1996, Preliminary seismic hazard assessment for Los Angeles, Ventura, and Orange counties, California, affected by the January 17, 1994 Northridge earthquake: Bulletin of the Seismological Society of America, v. 86, no. 1B, p. S247-S261.
- Shakal, A.F., Huang, M.J., Darragh, R.B., Cao, T.Q., Sherburne, R.W., Malhotra, P.K., Cramer, C.H., Sydnor, R.H., Graizer, Vladimir, Maldonado, G.O., Peterson, C.D. and Wampole, J.G., 1994, CSMIP strong-motion records from the Northridge, California earthquake of January 17, 1994: California Department of Conservation, Division of Mines and Geology, Office of Strong Motion Studies Report OSMS 94-07, 308 p.
- Smith, T.C., 1996, Preliminary maps of seismic hazard zones and draft guidelines for evaluating and mitigating seismic hazards: California Geology, v. 49, No. 6, p. 147-150.
- Treiman, J.A., unpublished, Landslide inventory of the Sunland 7.5-minute Quadrangle, Los Angeles County, California.
- U.S. Geological Survey, 1993, Digital Elevation Models: National Mapping Program, Technical Instructions, Data Users Guide 5, 48 p.
- Weber, F. H. Jr., 1982, Geology and geomorphology along the San Gabriel Fault Zone, Los Angeles and Ventura Counties, California: California Department of Conservation, Division of Mines and Geology Open-File Report 82-2, 157 p., map scale 1:24,000.
- Wilson, R.C. and Keefer, D.K., 1983, Dynamic analysis of a slope failure from the 1979 Coyote Lake, California, earthquake: Bulletin of the Seismological Society of America, v. 73, p. 863-877.
- Yerkes, R.F., 1996, Preliminary geologic map of the Sunland 7.5' Quadrangle, southern California: U.S. Geological Survey Open File Report 96-87, scale 1:24,000.
- Youd, T.L., 1980, Ground failure displacement and earthquake damage to buildings: American Society of Civil Engineers Conference on Civil Engineering and Nuclear Power, 2d, Knoxville, Tennessee, 1980, v. 2, p. 7-6-2 to 7-6-26.

AIR PHOTOS

- I.K.Curtis, 1971, photos, 5406-5420, 5429-5439, 5440-5482, 5504-5511, 5526-5533, 5550-5556, 5576-5583, 5603-5614, 5632-5643, 5796-5808, 5825-5838, 5852-5865, 5878-5891, 5903-5932, 5947-5962, 5974-5989, 6002-6077, 6221-6345, 6347-6361, 6367-6382, 6979-6984, 6987-6993, 6995-7001, 7003-7009, 7012-7024, 7046-7058, 7060-7076, 7079-7118, scale 1"=400'.
- United States Department of Agriculture (USDA), dated 12-4-52, Flight or Serial number AXJ, Photo numbers 7K-104-106, scale 1:20,000±.
- United States Department of Agriculture (USDA), dated 2-2-54, Flight or Serial number AXJ, Photo numbers 15K-1-8, scale 1:20,000±.

United States Department of Agriculture (USDA), dated 10-27-54, Flight or Serial number AXJ, Photo numbers 20K-21-24, 20K-33-37, scale 1:20,000±.

United States Department of Agriculture (USDA), dated 2-3-54, Flight or Serial number AXJ, Photo numbers 15K-28-33, 15K-69-74, 15K-77-82, scale 1:20,000±.

USGS (U.S. Geological Survey), 1994a, NAPP Aerial Photography, Flight 6858, May 31, 1994, Frame 19, black and white, vertical, scale 1:40,000.

USGS (U.S. Geological Survey), 1994b, NAPP Aerial Photography, Flight 6862, June 1, 1994, Frames 191-194 and 238-240, black and white, vertical, scale 1:40,000.

USGS (U.S. Geological Survey), 1994c, NAPP Aerial Photography, Flight 6866, June 1, 1994, Frames 147-149, black and white, vertical, scale 1:40,000.

APPENDIX A SOURCES OF ROCK STRENGTH DATA

(The numbers in parentheses are those tests taken from adjacent quadrangles)

SOURCE	NUMBER OF TESTS SELECTED
City of Los Angeles, Department of Building and Safety	97 (5)
Total number of tests used to characterize the units in the Sunland Quadrangle.	97 (5)

SECTION 3

GROUND SHAKING EVALUATION REPORT

Potential Ground Shaking in the Sunland 7.5-Minute Quadrangle, Los Angeles County, California

By

**Mark D. Petersen, Chris H. Cramer, Geoffrey A. Faneros,
Charles R. Real and Michael S. Reichle**

**California Department of Conservation
Division of Mines and Geology**

PURPOSE

The Seismic Hazards Mapping Act (the Act) of 1990 (Public Resources Code, Chapter 7.8, Division 2) directs the California Department of Conservation, Division of Mines and Geology (DMG) to delineate Seismic Hazard Zones. The purpose of the Act is to reduce the threat to public health and safety and to minimize the loss of life and property by identifying and mitigating seismic hazards. Cities, counties, and state agencies are directed to use the Seismic Hazard Zone Maps in their land-use planning and permitting processes. The Act requires that site-specific geotechnical investigations be performed prior to permitting most urban development projects within the hazard zones. Evaluation and mitigation of seismic hazards are to be conducted under guidelines established by the California State Mining and Geology Board (1997; also available on the Internet at <http://www.consrv.ca.gov/dmg/pubs/sp/117/>).

This section of the evaluation report summarizes the ground motions used to evaluate liquefaction and earthquake-induced landslide potential for zoning purposes. Included, are ground motion and related maps, a brief overview on how these maps were prepared, precautionary notes concerning their use, and related references. The maps provided herein are presented at a scale of approximately 1:150,000 (scale bar provided on maps), and show the full 7.5- minute quadrangle and portions of the adjacent eight quadrangles. They can be used to assist in the specification of earthquake loading conditions *for the analysis of ground failure* according to the “Simple

Prescribed Parameter Value” method (SPPV) described in the site investigation guidelines (California State Mining and Geology Board, 1997). Alternatively, they can be used as a basis for comparing levels of ground motion determined by other methods with the statewide standard.

This section and Sections 1 and 2, addressing liquefaction and earthquake-induced landslide hazards, constitute a report series that summarizes development of seismic hazard zone maps in the state. Additional information on seismic hazard zone mapping in California can be accessed on DMG’s Internet homepage: <http://www.consrv.ca.gov/dmg/shezp/>

EARTHQUAKE HAZARD MODEL

The estimated ground shaking is derived from the seismogenic sources as published in the statewide probabilistic seismic hazard evaluation released cooperatively by the California Department of Conservation, Division of Mines and Geology, and the U.S. Geological Survey (Petersen and others, 1996). That report documents an extensive 3-year effort to obtain consensus within the scientific community regarding fault parameters that characterize the seismic hazard in California. Fault sources included in the model were evaluated for long-term slip rate, maximum earthquake magnitude, and rupture geometry. These fault parameters, along with historical seismicity, were used to estimate return times of moderate to large earthquakes that contribute to the hazard.

The ground shaking levels are estimated for each of the sources included in the seismic source model using attenuation relations that relate earthquake shaking with magnitude, distance from the earthquake, and type of fault rupture (strike-slip, reverse, normal, or subduction). The published hazard evaluation of Petersen and others (1996) only considers uniform firm-rock site conditions. In this report, however, we extend the hazard analysis to include the hazard of exceeding peak horizontal ground acceleration (PGA) at 10% probability of exceedance in 50 years on spatially uniform conditions of rock, soft rock, and alluvium. These soil and rock conditions approximately correspond to site categories defined in Chapter 16 of the Uniform Building Code (ICBO, 1997), which are commonly found in California. We use the attenuation relations of Boore and others (1997), Campbell (1997), Sadigh and others (1997), and Youngs and others (1997) to calculate the ground motions.


The seismic hazard maps for ground shaking are produced by calculating the hazard at sites separated by about 5 km. Figures 3.1 through 3.3 show the hazard for PGA at 10% probability of exceedance in 50 years assuming the entire map area is firm rock, soft rock, or alluvial site conditions respectively. The sites where the hazard is calculated are represented as dots and ground motion contours as shaded regions. The quadrangle of interest is outlined by bold lines and centered on the map. Portions of the eight adjacent quadrangles are also shown so that the trends in the ground motion may be more apparent. We recommend estimating ground motion values by selecting the map that matches the actual site conditions, and interpolating from the calculated values of PGA rather than the contours, since the points are more accurate.

SUNLAND 7.5 MINUTE QUADRANGLE AND PORTIONS OF ADJACENT QUADRANGLES

10% EXCEEDANCE IN 50 YEARS PEAK GROUND ACCELERATION (g)

1998

FIRM ROCK CONDITIONS



Base map modified from MapInfo StreetWorks ©1998 MapInfo Corporation

0 2.5 5
Kilometers

Department of Conservation
Division of Mines and Geology




Figure 3.1

SUNLAND 7.5 MINUTE QUADRANGLE AND PORTIONS OF ADJACENT QUADRANGLES

10% EXCEEDANCE IN 50 YEARS PEAK GROUND ACCELERATION (g)

1998

SOFT ROCK CONDITIONS



Base map modified from MapInfo StreetWorks © 1998 MapInfo Corporation

0 2.5 5
Kilometers

Department of Conservation
Division of Mines and Geology




Figure 3.2

SUNLAND 7.5 MINUTE QUADRANGLE AND PORTIONS OF ADJACENT QUADRANGLES

10% EXCEEDANCE IN 50 YEARS PEAK GROUND ACCELERATION (g)

1998
ALLUVIUM CONDITIONS



Base map modified from MapInfo Street Works ©1998 MapInfo Corporation

0 2.5 5
Kilometers

Department of Conservation
Division of Mines and Geology

Figure 3.3



APPLICATIONS FOR LIQUEFACTION AND LANDSLIDE HAZARD ASSESSMENTS

Deaggregation of the seismic hazard identifies the contribution of each of the earthquakes (various magnitudes and distances) in the model to the ground motion hazard for a particular exposure period (see Cramer and Petersen, 1996). The map in Figure 3.4 identifies the magnitude and the distance (value in parentheses) of the earthquake that contributes most to the hazard at 10% probability of exceedance in 50 years on alluvial site conditions (*predominant earthquake*). This information gives a rationale for selecting a seismic record or ground motion level in evaluating ground failure. However, it is important to keep in mind that more than one earthquake may contribute significantly to the hazard at a site, and those events can have markedly different magnitudes and distances. For liquefaction hazard the predominant earthquake magnitude from Figure 3.4 and PGA from Figure 3.3 (alluvium conditions) can be used with the Youd and Idriss (1997) approach to estimate cyclic stress ratio demand. For landslide hazard the predominant earthquake magnitude and distance can be used to select a seismic record that is consistent with the hazard for calculating the Newmark displacement (Wilson and Keefer, 1983). When selecting the predominant earthquake magnitude and distance, it is advisable to consider the range of values in the vicinity of the site and perform the ground failure analysis accordingly. This would yield a range in ground failure hazard from which recommendations appropriate to the specific project can be made. Grid values for predominant earthquake magnitude and distance should **not** be interpolated at the site location, because these parameters are not continuous functions.

USE AND LIMITATIONS

The statewide map of seismic hazard has been developed using regional information and is ***not appropriate for site specific structural design applications***. Use of the ground motion maps prepared at larger scale is limited to estimating earthquake loading conditions for preliminary assessment of ground failure at a specific location. We recommend consideration of site-specific analyses before deciding on the sole use of these maps for several reasons.

1. The seismogenic sources used to generate the peak ground accelerations were digitized from the 1:750,000-scale fault activity map of Jennings (1994). Uncertainties in fault location are estimated to be about 1 to 2 kilometers (Petersen and others, 1996). Therefore, differences in the location of calculated hazard values may also differ by a similar amount. At a specific location, however, the log-linear attenuation of ground motion with distance renders hazard estimates less sensitive to uncertainties in source location.
2. The hazard was calculated on a grid at sites separated by about 5 km (0.05 degrees). Therefore, the calculated hazard may be located a couple kilometers away from the site. We have provided shaded contours on the maps to indicate regional trends of the hazard model. However, the contours only show regional trends that may not be apparent from points on a single map. Differences of up to 2 km have been observed between contours and individual


SEISMIC HAZARD EVALUATION OF THE SUNLAND QUADRANGLE
SUNLAND 7.5 MINUTE QUADRANGLE AND PORTIONS OF
ADJACENT QUADRANGLES

10% EXCEEDANCE IN 50 YEARS PEAK GROUND ACCELERATION

1998

PREDOMINANT EARTHQUAKE

Magnitude (Mw)
(Distance (km))



Base map modified from MapInfo StreetWorks ©1998 MapInfo Corporation

0 2.5 5
Kilometers

Department of Conservation
Division of Mines and Geology

Figure 3.4



ground acceleration values. *We recommend that the user interpolate PGA between the grid point values rather than simply using the shaded contours.*

3. Uncertainties in the hazard values have been estimated to be about +/- 50% of the ground motion value at two standard deviations (Cramer and others, 1996).
4. Not all active faults in California are included in this model. For example, faults that do not have documented slip rates are not included in the source model. Scientific research may identify active faults that have not previously been recognized. Therefore, future versions of the hazard model may include other faults and omit faults that are currently considered.
5. A map of the predominant earthquake magnitude and distance is provided from the deaggregation of the probabilistic seismic hazard model. However, it is important to recognize that a site may have more than one earthquake that contributes significantly to the hazard. Therefore, in some cases earthquakes other than the predominant earthquake should also be considered.

Because of its simplicity, it is likely that the SPPV method (California State Mining and Geology Board, 1997) will be widely used to estimate earthquake shaking loading conditions for the evaluation of ground failure hazards. It should be kept in mind that ground motions at a given distance from an earthquake will vary depending on site-specific characteristics such as geology, soil properties, and topography, which may not have been adequately accounted for in the regional hazard analysis. Although this variance is represented to some degree by the recorded ground motions that form the basis of the hazard model used to produce Figures 3.1, 3.2, and 3.3, extreme deviations can occur. More sophisticated methods that take into account other factors that may be present at the site (site amplification, basin effects, near source effects, etc.) should be employed as warranted. The decision to use the SPPV method with ground motions derived from Figures 3.1, 3.2, or 3.3 should be based on careful consideration of the above limitations, the geotechnical and seismological aspects of the project setting, and the “importance” or sensitivity of the proposed building with regard to occupant safety.

REFERENCES

- Boore, D.M., Joyner, W.B. and Fumal, T.E., 1997, Empirical near-source attenuation relationships for horizontal and vertical components of peak ground acceleration, peak ground velocity, and pseudo-absolute acceleration response spectra: *Seismological Research Letters*, v. 68, p. 154-179.
- California State Mining and Geology Board, 1997, Guidelines for evaluating and mitigating seismic hazards in California: California Department of Conservation, Division of Mines and Geology, Special Publication 117, 74 p.
- Campbell, K.W., 1997, Attenuation relationships for shallow crustal earthquakes based on California strong motion data: *Seismological Research Letters*, v. 68, p. 180-189.

- Cramer, C.H. and Petersen, M.D., 1996, Predominant seismic source distance and magnitude maps for Los Angeles, Orange and Ventura counties, California: Bulletin of the Seismological Society of America, v. 85, no. 5, p. 1645-1649.
- Cramer, C.H., Petersen, M.D. and Reichle, M.S., 1996, A Monte Carlo approach in estimating uncertainty for a seismic hazard assessment of Los Angeles, Ventura, and Orange counties, California: Bulletin of the Seismological Society of America, v. 86, p. 1681-1691.
- International Conference of Building Officials (ICBO), 1997, Uniform Building Code: v. 2, Structural engineering and installation standards, 492 p.
- Jennings, C.W., *compiler*, 1994, Fault activity map of California and adjacent areas: California Department of Conservation, Division of Mines and Geology, California Geologic Data Map Series, map no. 8.
- Petersen, M.D., Bryant, W.A., Cramer, C.H., Cao, T., Reichle, M.S., Frankel, A.D., Lienkaemper, J.J., McCrory, P.A. and Schwartz, D.P., 1996, Probabilistic seismic hazard assessment for the State of California: California Department of Conservation, Division of Mines and Geology Open-File Report 96-08; also U.S. Geological Survey Open-File Report 96-706, 66 pp.
- Sadigh, K., Chang, C.-Y., Egan, J.A., Makdisi, F. and Youngs, R.R., 1997, SEA96- A new predictive relation for earthquake ground motions in extensional tectonic regimes: Seismological Research Letters, v. 68, p. 190-198.
- Wilson, R.C. and Keefer, D.K., 1983, Dynamic analysis of a slope failure from the 1979 Coyote Lake, California, Earthquake: Bulletin of the Seismological Society of America, v. 73, p. 863-877.
- Youd, T.L. and Idriss I.M., 1997, Proceedings of the NCEER workshop on evaluation of liquefaction resistance of soils: Technical Report NCEER-97-0022, 40 p.
- Youngs, R.R., Chiou, S.-J., Silva, W.J. and Humphrey, J.R., 1997, Stochastic point-source modeling of ground motions in the Cascadia Region: Seismological Research Letters, v. 68, p. 74-85.

B = Pre-Quaternary bedrock.

ONE MILE
SCALE





Plate 1.2 Historically Highest Ground Water Contours and Borehole Log Data Locations, Sunland Quadrangle.

● Borehole Site — 30 — Depth to ground water in feet

1 Site of historical earthquake-generated liquefaction. See "Areas of Past Liquefaction" discussion in text.

ONE MILE
SCALE



Base map enlarged from U.S.G.S. 30 x 60-minute series

Plate 2.1 Landslide inventory, Shear Test Sample Locations, and Areas of Significant Grading, Sunland Quadrangle.

- shear test sample location
- landslide
- ▧

areas of significant grading

ONE MILE

SCALE